

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019

Resetting of chainlink fencing, implementation of Rain water harvesting and improvements to park at TATA Nagar park in ward no 08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PUTTARAJU A ()	
				In Figures	In Words
1	57.5	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.143, I.No.19.1 of PW, P&IWD SR 2018-19)	Cum	252.0	Rupees Two Hundred Fifty Two Only
2	5.94	KSRRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 16, item No : 4.28)	Sqm	273.0	Rupees Two Hundred Seventy Three Only
3	44	Providing and laying in position plain cement concrete of Mix CC 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation including cost of all materials, labour HOM of machinery curing complete as per specification, specification No. KBS 4, 1, 4.2 (PageNo.13, Item No.4.3)	Cum	5206.0	Rupees Five Thousand Two Hundred Six Only
4	220	Providing and fixing cement base precast, pre-polished cement concrete designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, gridding the edge to half/full round wherever required, labour curing complete as per specification. (P.112, I. No.14.62)	Sqm	1305.0	Rupees One Thousand Three Hundred Five Only
5	0.45	KSRRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, in foundation and plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.(P.No.13, I.No. 4.5 of PWD SR 2018-19)	Cum	5647.0	Rupees Five Thousand Six Hundred Forty Seven Only
6	55	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (P.No.266 I.No.37.2 of PW,P&IWD SR of 2018-19)	m	910.0	Rupees Nine Hundred Ten Only
7	110	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (P.No.266 of I.No.37.3 in PW,P&IWD S.R 2018-19)	Sqm	757.0	Rupees Seven Hundred Fifty Seven Only
8	132	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. (P.No.266 I.No.37.4 of PW,P&IWD SR of 2018-19)	m	432.0	Rupees Four Hundred Thirty Two Only


Signature of the contractor

Page 1 of 2

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PUTTARAJU A ()	
				In Figures	In Words
9	525.12	KSRRB M800-7. Painting:-Providing and applying two coats of ready-mix paint of approved brand after thorough cleaning of surface to give an even shade complete as per specifications. MORTH Specification No. 803 Painting on Steel Surface(P.No.181, I.No.24.8.1 of PW,P&IWTD S.R 2018-19)	Sqm	76.0	Rupees Seventy Six Only
10	55.1	KSRRB M400-19: Construction of Median and island above road level with approved material deposited from borrowpits, spread, sloped and compacted as per Clause 400.7 complete as per specifications. MORTH Specification No.407 (P.No.155 of I.No.20.20 in PW,P&IWTD SR 2018-19)	cum	221.0	Rupees Two Hundred Twenty One Only
11	331	KSRRB 14.6-1: Providing & laying heavy duty cobble stones 60mm thick interlock pavers, using cement & coarse sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (Avg thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No. 103 of I.No.14.6 in PW,P&IWTD SR 2018-19)	Sqm	1116.0	Rupees One Thousand One Hundred Sixteen Only
12	111.79	Removing and resetting of kerb stones(P.No.270, I.No.37.57 of PW,P&IWTD SR 2018-19)	m	104.0	Rupees One Hundred Four Only
13	1662	Providing and fixing precast solid concrete kerb stones made out of CC. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete (P. No. 27 I. No.5.29.2 in PW,P&IWTD SR 2018-19)	No	467.0	Rupees Four Hundred Sixty Seven Only
14	669.06	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No.180, I.No. 24.1 of PW,P&IWTD SR 2018-19)	Sqm	84.0	Rupees Eighty Four Only
15	10	Providing and making precast seating arrangement including excavation laying pcc M15, providing laying M20 concrete for pedestal and seating slab, fixing of seating slab including all necessary bolt and nuts etc, complete and as per the directions of Engineer in-Charge. (Data Rate)	Sqm	11785.0	Rupees Eleven Thousand Seven Hundred Eighty Five Only
16	4	Providing Rainwater harvesting pits for Parks	No	21000.0	Rupees Twenty One Thousand Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92


6/03